

Addendum No. 1 September 29, 2017

This bid page replaces previous version and will be used for bid submittal.

All other parts of the bid remain in effect

Item No.	DESCRIPTION	Estimated Quantity	UNIT	Unit Price	TOTAL
1	1901 Elm St. Driveway approach repair	19	Sq. Yds.	\$	
2	216 Bryant Pl. Concrete parking repair	9	Sq. Yds.	\$	
3	225 Bryant Pl. Concrete parking repair	26	Sq. Yds.	\$	
4	3316 SE 15th Concrete parking repair	9	Sq. Yds.	\$	
5	3901 se 27 th Driveway Approach repair	17	Sq Yds..	\$	
6	3104 Hillside Driveway Approach repair	17	Sq. Yds.	\$	
7	4749 Woodview Concrete Street repair	36	Sq. Yds.	\$	
8	SE 24 th & Vickie (2 Places) Sidewalk repair	16	Sq. Yds.	\$	
9	Se 15 th & Sunnyside Concrete curb repair Match existing	8	Lin. Ft.	\$	
10	Larkwood & Veterans Concrete curb repair Match existing	3	Lin. Ft..	\$	
11	3605 Terry Way Sidewalk repair	11	Sq. Yds.	\$	
12	2116 Sunnyside Sidewalk repair	5	Sq. Yds.	\$	
13	4304 Sunnyside Circle Concrete street repair	17	Sq Yds	\$	
14	717 Howard 28" Curb & Gutter	140	Lin. Ft.	\$	
15	717 Howard Asphalt street repair w/ 8" of 1 1/2" crusher run base, fabric reinforcing, 3" A mix & 2" B mix cap.	83	Sq. Yds.	\$	
16	3040 Del View Concrete street repair	40	Sq. Yds.	\$	
17	Intersection of 29 th & Epperly South side approach Replace asphalt with 6" of Concrete	70	Sq. Yds.	\$	
18	4500 SE 29 th Pavement repair 8" of 1 1/2" crusher run, 6" of concrete & 2" B mix asphalt.	68	Sq. Yds.	\$	
19	Intersection of Ridgeway & Vickie Concrete street repair	107	Sq. Yds.	\$	
20	4100 SE 26 th Concrete street repair	60	Sq. Yds.	\$	
21	4200 SE 26 th Concrete street repair	112	Sq. Yds.	\$	
22	4213 SE 26 th Concrete street repair	52	Sq. Yds.	\$	
23	1630 S Sunnyside 24" Concrete curb & gutter repair	24	Lin. Ft.	\$	
24	SE 44th & Leonhardt Grout Channel Bottom	15	Cu. Yds.	\$	
25	4413 SE 41st Concrete street repair	4	Sq. Yds.	\$	
26	3508 Hartsdale Concrete street repair	45	Sq. Yds.	\$	

27	Intersection of Princess & Hartline Concrete Street Repair	27	Sq. Yds.	\$	
28	3520 Hillside Concrete Street Repair	100	Sq. Yds.	\$	
29	1412 Shalamar Concrete street repair	93	Sq. Yds.	\$	
30	Labor only to install dowels		Per.	\$	
	TOTAL BASE BID				

All Dowels and expansion joint material provided by the City.